PEOPLE'S TELEVISION
PARA SA BAYAN
People's Television Network, Inc
Broadcast Complex, Visayas Avenue, Diliman, Quezon City 1100
Telephone No. 3453-1097 /www.ptv.ph

BID BULLETIN NO. 1

13 February 2020

Supply, Delivery, Testing and Commissioning of Broadcast Transmitter Tower Lightning and Grounding System Rehabilitation for the People's Television Network, Inc. (PTNI)
ITB NO. 2020-0004

This bulletin is issued to modify or amend items in the bidding documents. This shall form an integral part of the bidding documents.

No	PROJECT NAME	SCHEDULE
1	Does PTV have definite design for the grounding system of project? In case there is, please provide us. The ITB technical specs indicate minimum technical requirements but no detailed design grounding system. If no detailed design grounding system and let bidders to offer their preferable design, it will not be comparable (apple to apple) to each of bidders. Unlike there is common design from procuring entity, each bidders will quote on single design and all bids can be compared easily.	Does PTV have a definite design for the grounding system? **Yes** In case there is, please provide us. T**he bidder shall provide its own design.** The ITB technical specs indicate minimum technical requirements but no detailed design grounding system. **Yes, because the existing system is still working.** If there is no detailed design grounding system and the bidders will offer their preferred design, it will not be comparable (apple to apple) to each of bidder. **Yes, as stated on 2. Scope of work 2.2 The provider/bidder is required to check/evaluate the existing status of transmitter tower lightning protection and grounding system and submit a report with supported colored pictures on hard/soft copy file before and after from start to finish. It must be included in the bid.** Unlike other projects, there is a common design from procuring entity. Each bidder will quote on a single design and all bids can be compared easily. **Common design and system is still in-use and the need to upgrade.**
2	Since there is a word "rehabilitation" in the schedule of requirements, this means, some existing items need not necessary be replaced, or upgraded and those existing can be reused?	**Yes, as long as it's replaced with a better one.**

4	Is it allowed to set up a temporary facility (bunk house for manpower, tools, and materials) in the premises of PTV? Or we have to lease a place outside the premises?	**No, bunk house for manpower inside the PTV premises is not allowed** **The procuring entity will provide a place where the tools and materials of the winning bidder will be stored.**
5	Is it allowed to use the power and water source of PTV during implementation? Free or with charge?	**Yes the winning bidder may use the power and water source but shall shoulder the usage costs. The winning bidder shall have a sub meter installed.**
6	Since this is inside premises of PTV, who will process the working permit? Or is it necessary to have it?	**The winning bidder shall process all the working permits.**
7	We just want to ask if what your good office preferred, If it's the dissipator arrestor or it is acceptable if we offer the lightning arrester E.S.E.? Thank You.	**We prefer a Dissipator Arrestor.** **No, we are not accepting the E.S.E lightning arrester**
8	Do you have power source in the Transmitter Tower that we can use for the lights.	**There is no available power source at the transmitter tower.** **Please be advise of the following regarding the power line:** - **There shall be a line with breaker for one (1) beacon & four (4) side lights in a IRC metal conduit pipe and;** - **A separate line with breaker for two (2) spotlights in a IRC metal conduit pipe.**

No	Amendment	
	From	To
1	Similar contract shall refer to Broadcast and Telecom Tower Grounding Installation	Similar contract shall refer to **Broadcast and/or Telecom Tower Lightning and Grounding system installation**

Please be advice regarding the Site Inspection and Evaluation Reports
Site inspection is required for this project For those interested bidders: We are scheduling a Site Inspection this coming 18th of February 2020 at exactly 9:00 AM to evaluate the existing tower lightning and grounding system. The evaluation report shall also be submitted during the opening of bids. You may get the Certificate of site inspection after the inspection from the BAC Secretariat For the bidders from last bidding (ITB NO. 2019-0016) We are acknowledging those prospective bidders who already have the evaluation report and conducted site inspection from the last bidding. You may claim your site inspection from BAC Secretariat.

PEOPLE'S TELEVISION
PARA SA BAYAN
People's Television Network, Inc
Broadcast Complex, Visayas Avenue, Diliman, Quezon City 1100
Telephone No. 3453-1097 /www.ptv.ph

All other information in the Bidding Documents inconsistent with the above are hereby revised accordingly. All other provisions which are not affected shall remain in effect.

For further guidance and information of all concerned.

Thank you.

MARIA ANGELA C. GATAN
Chairperson,
Bids and Awards Committee