BID BULLETIN NO. 2
August 3, 2021

Supply, Delivery, Installation, Integration Testing, Training and Commissioning
of Two (2) Sets of Studio Teleprompter System with Complete Accessories for Studio A & B of
People's Television Network, Inc.
ITB NO. 2021-0005

This bulletin is being issued to revise/clarify certain portions of the bidding documents. This shall form an integral part of the bidding document for the above-stated project.

No.	Comments/Queries/Concerns	Response
1	In Item No. 1 "Two (2) Sets of Studio Teleprompter System with Complete Accessories including integration to existing NPAS of PTNI" The following Items after "Item 1" are the accessories included in completing the system of the Teleprompter System. Please clarify the accessories included in "Item 1"?	"Complete Accessories" is defined as all necessary accessories for the Teleprompting System must be included such as Hardware and Softwares needed.
2	It said that the Teleprompter System will be used in the News and Production Studio Does the supplied Teleprompter System need to be integrated into the existing Teleprompters?	No, the required Teleprompters will be a complete system to be integrated only to the existing Camera and Camera Pedestal System, Production Control Room switcher, Monitoring, and NPAS.
3	News Studio and Production Studio will each have a set of Teleprompter System?	Yes.
4	Is Item No. 3 "Camera Mounted Monitor with frames and mirror" Is this a Talent Monitor?	No, it is a Teleprompter LCD display, the one that is mounted in the Camera Pedestal and with a reverse display.
5	Clarification on Item No. 2 "Input/output Box" Normally this is already incorporated/built-in in a Teleprompter System with glass and processor, Does it mean that a separate Input/Output Box is needed?	If the Technology of the offered Teleprompter System does not need the video interface Input/Output box. it is acceptable, provided that the Teleprompter Signal shall pass through Camera Control Unit Teleprompter BNC input.
6	On page 18, Bid Data Sheet, ITB Clause 5.3. *For this purpose, contracts similar to the Project shall be:* *a. Supply, Delivery, Testing, Commissioning and Installation on News Television Studio Teleprompting System."* May we add or consider "or Broadcast Equipment"?	Similar Project hereby revised to: Supply, Delivery, Testing, Commissioning, and Installation of News Television Studio Teleprompting Systems or Video Equipment for Television Broadcast."

People's Television
P A R A   S A   B A Y A N

People's Television Network, Inc
Broadcast Complex, Visayas Avenue, Diliman, Quezon City 1100
Telephone No. 3453-1097 /www.ptv.ph

7	On page 31, Delivery Period under Schedule of Requirements; Thirty (30) calendar days upon the receipt of Notice to Proceed. May we request to extend up to Seventy five (75) calendar days upon the receipt of Notice to Proceed. For the reason that there is a global shortage of microchips due to the pandemic.	Delivery Period is hereby revised to: Forty-Five (45) Calendar Days.
8	Item 2 & 3, there are specified interface ports like (SDI-HD, HDMI, VBS, & Genlock) The Technology now is in IP Connectivity, is it okay to reduce the required interface ports? Is it okay to consider SDI only for the camera?	IP Connectivity is very much acceptable since that is a new technology, provided that the bidder shall include all needed converters for the system integrations at their own costs. The Camera Control Unit Interface of the existing Camera Systems is BNC HD-SDI and VBS Analog. also it must be locked-on in the System using Tri-Level Sync.
9	What we have is IP Connectivity, VNC Port, SDI-HDI due to the latest technology. What about the other required interfaces?	IP Connectivity is very much acceptable since that is a new technology, provided that the bidder shall include all needed converters for the system integrations at their own costs. Camera Control Unit Interface of the existing Camera Systems is BNC HD-SDI and VBS Analog. also it must be locked-on in the System.
10	With regards to the Submission of Bid on 11 August 2021, Is this going to push through considering the announcement of ECQ?	Yes, since the equipment is needed immediately. On the Opening of Bids, we discourage the presence of bidders physically and recommend participating virtually due to the office safety protocols.
11	Will you consider the absence of the Genlock in the supplied item since Genlock is not necessary for prompter nowadays? Whether the equipment supplied is with or without Input/ Output box.	It's okay as long as it is locked-on in the studio system.
12	With regards to the Similar Project Can you consider "Audio and Visual Equipment"?	Similar Project hereby revised to: Supply, Delivery, Testing, Commissioning, and Installation of News Television Studio Teleprompting Systems, or Video Equipment for Television Broadcast.
13	In item 3 "Camera Mounted Monitor with frames and mirror" Will you consider the brightness (1000 cd/m2) and a resolution of 1280 x 1024 of the prompting monitor, instead of the full resolution(1920 x 1080) HD which is only available on 21" prompting monitors?	Camera mounted monitors size must be the same with the reflected mirror image size in full HD 1920x1080.

PEOPLE'S TELEVISION
P A R A   S A   B A Y A N

People's Television Network, Inc
Broadcast Complex, Visayas Avenue, Diliman, Quezon City 1100
Telephone No. 3453-1097 /www.ptv.ph

14	On page 33, Item 2 Specification under Technical Specifications I/O Box with at least
	  Input:
	    - SDI-HD
	    - HDMI
	    - VBS
	    - Genlock
	  Output:
	    - 2 x HD/SDI
	    - HDMI
	    - Composite VBS
	
	May we request relaxing of the below specification;
	  Input:
	    - 1 x RJ45 Ethernet
	  Output
	    - 2 x HD-SDI
	    - 1 x RJ45 PoE
	
	The configuration comes with an interface box which directly communicate to the teleprompter monitor
		IP Connectivity is very much acceptable since that is a new technology, provided that the bidder shall include all needed converters for the system integrations at their own costs.
		Camera Control Unit Interface of the existing Camera Systems is BNC HD-SDI and VBS Analog. also it must be locked-on in the System.

15	On page 33 & 34, Item 3 Specifications under Technical Specifications. It must be light weight, complete sets the Camera mounted monitor must be full High Definition 1920x1080, at least 15 inches and must be capable for following inputs: - SDI-HD HDMI VBS Genlock May we request below specifications; - 15" monitor with 1024x768 resolution - 2 x HD-SDI 2 x CVBS LAN input The prompter monitor display which contains text only, doesn't require a high video resolution.	Camera mounted monitors size must be the same with the reflected mirror image size in full HD 1920x1080.

![People's Television logo]
PEOPLE'S TELEVISION
P A R A S A B A Y A N

People's Television Network, Inc
Broadcast Complex, Visayas Avenue, Diliman, Quezon City 1100
Telephone No. 3453-1097 /www.ptv.ph

For Reference here is the picture of the existing camera and pedestal system of PTNI

Existing Studio Camera System

All other information in the Bidding Documents inconsistent with the above is hereby revised accordingly. All other provisions which are not affected shall remain in effect.

For further guidance and information of all concerned.
Thank you.

ATTY. JASON SHAHEER H. SALENDAB
Chairman
Bids and Awards Committee