

People's Television Network, Inc. Broadcast Complex, Visayas Avenue, Diliman, Quezon City 1100 Telephone No. 3453-1097/www.ptni.gov.ph

## REQUEST FOR QUOTATION SVP No. 2022 – 0015

17 March 2022

The People's Television Network, Inc. (PTNI), through its Bids and Awards Committee (BAC), invites interested bidders for the Small Value Procurement of Supply and Delivery of One (1) unit 25 KVA Isolation Transformer and Electrical Materials for Uplink Equipment Power Supply. The details of the project are as follows:

| A .Name of the Project                     | Supply and Delivery of One (1) unit 25 KVA Isolation Transformer and Electrical Materials for Uplink Equipment Power Supply.   |  |  |  |
|--|--|--|--|--|
| B Source of Fund:                          | MOOE   |  |  |  |
| C. Approved Budget for the Contract (ABC): | Ninety-Nine Thousand Seven Hundred<br>Forty-Three Pesos Only. (Php99,743.00)   |  |  |  |
| D. Mode of Procurement:                    | Procurement will be conducted in accordance with Sec.53.9 (Small Value Procurement) of the Revised Implementing Rules and Regulations of Republic Act 9184, otherwise known as "The Government Procurement Reform Act"   |  |  |  |
| E. Documentary Requirements:               | Copies of the following eligibility requirements are also required to be submitted along with your quotation/proposal:  1. Mayor's/Business Permit (2022) 2. PhilGEPS Registration Number 3. Income/Business Tax Return (2020-stamped 2021) 4. Omnibus Sworn Statement (duly notarized) *only the BIR Certificate of Registration shall be submitted in lieu of DTI Registration and Mayor's Permit. |  |  |  |

Only Sealed bids/ or E-mail quotations from the eligible bidders will be opened and a contract will only be awarded to the Lowest Calculated and Responsive Bidder who was determined as such during post qualification.

Payment: within 30 calendar days after completion and acceptance.

**Price Validity:** All price quotations shall be considered as fixed prices and not subject to price escalation during contract implementation.

Delivery Period: Within fourteen (14) calendar days from receipt of Notice to Proceed.

#### F. Description:

Supply and Delivery of One (1) unit 25 KVA Isolation Transformer and Electrical Materials for Uplink Equipment Power Supply.

\*Please see attached for the T.O.R. (Terms of Reference)

Bids received in excess of the ABC shall be automatically rejected at the opening of quotations.

Sealed or E-mail quotations may be submitted on or before 10:00am, 28 March 2022, at the Purchasing Office, Broadcast Complex, Visayas Avenue, Diliman, Quezon City or thru Email add: <a href="mailto:purchasingsection@yahoo.com">purchasingsection@yahoo.com</a>, respectively.

The PTNI reserves the right to accept or reject any bid to annul the bidding process and to reject all bids at any time prior to contract award without thereby incurring any liability to the affected bidder or bidders.

MARIE THERESE D. NICOLA Chairperson, BAC II-SVP

# TECHNICAL SPECIFICATION

# Supply and Delivery of 1 unit 25 KVA Isolation Transformer and Electrical Materials for Uplink Equipment Power Supply

## I. Transformer Specification

| Unit | Specification   | Qty | Delivery              | Statement of<br>Compliance |
|------|---|-----|-----------------------|----------------------------|
| Unit | 25Kva Isolation Transformer, Primary : 460-480Volts Multi-Tap L-L Secondary : 220-230 Volts L-L Phase ; 3Ø Frequency : 50-60Hz Class : H Conductor : Copper Configuration: DELTA-WYE w/ Faraday Shields Taps (offload) : 2x2.5%FCAN / 4x2.5% FCBN Core Made: Non-aging grain-oriented silicon steel | 1   | 14<br>Working<br>days |                            |

## II. Electrical Materials

| Unit | Specification   | Qty  | Delivery           | Statement of<br>Compliance   |
|------|---|--|--------------------|--|
| Set  | Main Circuit Breaker, Industrial Type, 100AT,<br>3 Pole, 480volts, 60Hz, w/Enclosure NEMA I | - Annual Control of the Control of t | 14 Working<br>days |  |
| mtrs | 14mm <sup>2</sup> THW Electrical Wire   | 30   | 88                 |  |
| mtrs | Flexible Metal Conduit (FMC) Ø1"  | 30   | 44                 | A CONTRACTOR OF THE CONTRACTOR |
| pcs  | FMC Straight Connector w/lock nut and Bushing Ø1"   | 10   | £\$                |  |
| pcs  | Copper Terminal Logs size 1/0"  | 10   |                    |  |
| box  | Metal Tox w/screw #6  | 1  | н                  |  |
| pcs  | Electrical Tape Big   | 5  | 16                 |  |
| pcs  | Hacksaw Blade   | 5  | и                  |  |

## III. Manufacturer Essential Pre-requisite

- a) The item must be Brand New/First-hand newly assembled unit, not a second-hand unit and not a recycled or retrofit material used in the assembly.
- b) Must provide and submit Transformer Testing Data
- c) Must provide and submit a picture during unit assembly and testing with QA/QC inspection.

- d) Manufacturer representatives present during transformer test run or fire up. This is to check, attest and witness the unit functionality and operation. This is to avoid a misconception in case unit failure to run or operate.
- e) A Warranty Certificate must provide with a content of free service repair, replacement and duration of warranty service period.

#### IV. Warranty

1. It Depends upon Manufacturer Warranty Service

#### V. Delivery Period

1. 14 Working Days

Prepared by:

Melandro J. Royulada/Dolgie M. Fruelda

**Building and Grounds** 

Noted by:

Ms. Maila E. Mamaril

OIC, Admin Division