

PURCHASE ORDER

PTV

(People's Television Network, Inc.)

Broadcast Complex, Visayas Avenue, Diliman, Quezon City

Tel Nos. 453-1097/455-2718

Supplier : V.B. Powernet Electrical & Industrial Supply	P.O. No.: 22-04-0010
Address : 61 Ilang-Ilang St., Pingkian III, Brgy. Pasong Tamo, Quezon City	Date : April 8, 2022
Tel no./TIN (8994-4069/3427-7356) 150-823-967-000	P.R. No.: 22-03-0220
Mode of Procurement: Small Value Procurement-SVP No. 2022-0015	Date : March 10, 2022

Gentlemen:


Please furnish this Office the following articles subject to the terms and condition contained herein:

Place of Delivery : PTNI, Broadcast Complex, Visayas Ave., Diliman, QC	Delivery Term :
Date of Delivery : within ten (10) working days	Payment Term : 30 days

Unit	Description	Quantity	Unit Cost	Amount
unit	Small Value Procurement - SVP No. 2022-0015 Supply and Delivery of One (1) unit 25KVA Isolation Transformer and Electrical Materials for Uplink Equipment Power Supply Dry Type Transformer (Offer: Powernet), 3Phase, 60Hz * Capacity : 25KVA * Primary : 460V * Taps (offload) : 2x2.5%FCAN/ 4x2.5% FCBN * Secondary : 230v * Temp. Rise : 150°C at 40°C ambient * Insulation : Class H Insulation (220°C Fiberglass) * Configuration : DELTA-WYE w/ Faraday Shields * Conductor : All copper windings * Core Made : Non-aging grain oriented silicon steel * Casing : Ventilated (Nema 1 Powder Coated) * Dimension : 26" x 18" x 26" (H x W x L) * Weight : 180kgs. <i>Warranty: One (1) year. Guaranty does not include cause by natural calamities, mis used and improper installation</i>			80,800.00
unit	MCB, NEMA I, 100Amps, 480v, 3pole, industrial type (Offer: Schneider brand)	1		7,500.00
mtrs.	THHN 14mm sq. Stranded wire (Philflex)	30	168.00	5,040.00
mtrs.	Flexible Metallic conduit (FMC) 1" dia.	30	92.00	2,760.00
pcs.	FMC Connector 1" dia	10	72.00	720.00
pcs.	Crimp type terminal lugs 1/0	10	61.00	610.00
pcs.	PVC Armak tape 3/4	5	52.00	260.00
box	Metal tox screw #6			650.00
(Total amount in Words) ninety eight thousand three hundred forty pesos only				98,340.00

In case of failure to make the full delivery within the time specified above, a penalty of one-tenth (1/10) of one percent for every day of delay shall be imposed.

Very truly yours,


KATHERINE CHLOE S. DE CASTRO
 Authorized Official

Conformer:



VIRGILIO R. BACQUEL JR.

Signature over Printed Name of Supplier

04/19/22

Date

Funds Available: